

Produced Water Degassing Package - Process Datasheet

Document No.:	LIB-PRO-0019
Revision:	A
Discipline:	Process
Document Type:	Datasheet
Date:	2026-06-02
Project:	FPSO Liberty Development

Description

This datasheet defines the process design conditions for the produced water degassing package upstream of the hydrocyclone train, including design flow rate, operating pressure and temperature envelopes, and expected oil-in-water concentration at inlet.

Package sizing is based on the sustained production case identified in the Process Design Basis. Turndown performance down to 30% of design flow shall be demonstrated during FAT.